TUMKUR DIVISION.

Dated 28th December 1911.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 15th January 1912, for constructing a second block of eight rooms to the Students' Home at Tumkur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M., and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred in cash or Government promissory notes, as earnest money, and be superscribed "Tender for Students' Home at Tumkur," in default of which, tenders will be rejected.

5. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of the tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate of the probable quantity of constructing another block of eight rooms in the Students' Home attached to the High School at Tumkur.

Items of work	*Per*	*Quantity*
Earthwork, excavation and filling in basement ...	C. yds.	102
Concrete foundation	C. ft.	716
Burnt stone in chunam	„	2,395
Burnt brick in chunam	„	4,131
Burnt brick in chunam, arch work	„	16
Burnt stone slabs	Sq. ft.	938
Armoured concrete pillars, 8″×8″ square with chamfered edge with base, capital, armouring, etc., complete ...	No.	11
Chunam plastering	Sqr.	92·93
White and colour-washing	„	92·93
Chunam pointing	„	4·69
Cuddapah slab flooring, 1½″ thick over 3″ concrete and cement pointing	„	21·78
Teakwood work wrought and put up	C. ft.	277·69
Roofing with 1st class Mangalore tiles with teak reepers, with filling, etc., complete	Sq.	37·13
Ridge tiles set in mortar	R. ft.	135
Teakwood battened doors with double shutters, 1¼″ thick plank with fitting, etc., complete including iron hold-fasts or clamps	S. ft.	156
Teakwood windows, inside glazed, outside panelled shutters, cut in four parts with ⅝″ iron bars, hinges and nails	„	192
Teakwood windows half panelled and half glazed with iron bars and hold-fasts, complete	„	96
Shelves in walls with battened shutters for the lover half, including locks, etc.	„	144
Teakwood finials at gable ends	Each	2
Ornamental eaveboards 9″	R. ft.	270
Silicate painting	Sq.	14·18
Teakwood planks for shelves 1″ thick	S. ft.	162
Cornice work, plain	R. ft.	44
Teakwood trellis work	S. ft.	19
Dwarf walls at gable ends	R. ft.	54
Pegs, iron, 3 for each block, 9″ thick long and ⅝″ diameter	lb.	64B
Tarring wood work in the wall	L. S.	Rs.
Removing present zinc store shed and refixing with old materials with masonry works, etc., complete ...	„	„
Dismantling coping	„	„
Wood-oiling wood work	Sq.	23·97
Constructing a latrine...	L. S.	Rs.

Abstract Notification.

The attention of the public is invited to the Notification dated 21st December 1911, calling for tenders for restoring Ammasandra Tank R. No. 236, Gubbi Taluk, Tumkur District.

K. PONNAPPA,
Executive Engineer.

CHITALDRUG DIVISION.

Dated 30th December 1911.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 25th January 1912, for constructing a third class travellers' bungalow at Aiyamangala, Hiriyur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing a third class Travellers' Bungalow at Aiyamangala, Hiriyur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing a third class Travellers' Bungalow at Aiyamangala, Hiriyur Taluk.

Item No.	*Details of work*	*Per*	*Quantity*
1.	Earthwork, excavation and filling basement	C. yd.	165
2.	Stone jelly concrete, filling foundation	C. ft.	1,865
3.	Burnt or trap stone in chunam, foundation	,,	3,526
4.	Burnt brick in chunam	,,	5,281
5.	Archwork	,,	57
6.	Burnt stone slabs, dressed	S. ft.	702
7.	Plastering with chunam	Sqr.	83·92
8.	White and colour-washing	,,	85·42
9.	Pointing with chunam	,,	5·54
10.	Teakwood work with wood-oiling, wrought and put up complete	C. ft.	148·19
11.	Roofing with 1st class Mangalore tiles with teak reapers	Sqr.	30·57
12.	Mangalore ridge tiles set in mortar	R. ft.	104
13.	Mangalore glazed tiles	Each	4
14.	Mangalore ventilating tiles	,,	10
15.	Cut stone pillars with cap and base complete	,,	6
16.	Flooring with Mangalore tiles over 3" concrete and cement pointing	Sqr.	7·00
17.	Flooring with Cuddapah slabs over 3" concrete and cement pointing	,,	7·86
18.	Flooring with Cuddapah slabs over 6" sand and cement pointing	,,	1·09
19.	Silicate painting two coats with one coat of varnish	,,	7·25
20.	Wood-oiling two coats and one coat of varnish	,,	5·46
21.	Ornamental eaveboard 10" wide	R. ft.	85
22.	Teakwood doors panelled with iron clamps for fixing, complete	S. ft.	154
23.	Teakwood doors with double shutters with iron clamps fixed	,,	28
24.	Teakwood doors (battened) with iron clamps fixed, complete	,,	147
25.	Teakwood windows, inside glazed, outside panelled, with iron bars and iron clamps fixed, etc., complete	,,	63